




# Proposed Scope for Focused Cleanup of Plainwell No. 2 Dam Area

April 13, 2009





# Background

- KRSG, USEPA, MDEQ, and Natural Resource Trustee met 10/07/08 to review KRSG's proposed *Next Steps for Cleanup and Restoration of the Kalamazoo River*
  - Included scope for cleanup of Plainwell No. 2 Dam Area
- *Conceptual Design Report for Bank Removal and Restoration – Plainwell No. 2 Dam Area* (CDR) submitted to USEPA 11/04/08
- A meeting was held 12/04/08 to discuss Agencies' review of the CDR
- Additional data from MDEQ forwarded to KRSG on 12/29/08
- A planned January 2009 meeting to complete scope discussions was canceled by Millennium Holdings, LLC
- ARCADIS reconnoitered Island 2 side channel area in February 2009
- This updated proposed scope for jointly funded cleanup agreement with USEPA was modified in response to Agency comments on the initial proposal, and additional information from MDEQ




# Summary of Scope Adjustments from Conceptual Design Report

- Information from MDEQ was incorporated to generate updated cumulative mass removal basis for targeting bank segments
  - New bank segments included near the Dam, Island 2 side channel
  - PCB mass removal increased to 92% of available inventory
  - Bank removal increased to 53% of total length
- 0.9-acre floodplain area near mouth of oxbow with 44 (J) mg/kg PCB in the surface soil (0 to 0.5-foot interval) included
- Remaining floodplain and bank soil PCB concentrations average 2.3 mg/kg with a median of 1.3 mg/kg
- 0.9-acre sediment area on west side of oxbow included down to midpoint between sediment samples P2RT7-7 and P2RT8-7
- Removal of toe-of-bank sediments in specific areas
  - To be determined in design based on individual transect information
  - Allowed for using 1.5 ft<sup>2</sup> cross-sectional excavation along length of removed bank




# Proposed Removal Areas






# Removal Scope: Proposed Bank Soil PCB Mass Removal





# Removal Scope: Proposed Bank Soil PCB Mass Removal





# Scope Summary

Parameter	Extent of Removal
Bank Length	2.1 miles
Bank Area	7.1 acres
Bank Soil Volume	11,200 cy
Floodplain Area	0.9 acres
Floodplain Volume	780 cy
Sediment Volume	2,290 cy
<b>TOTAL VOLUME</b>	<b>14,270 cy</b>




# TSCA Disposal Requirements

- **Application of Fox River Protocol**
  - Depth-weighted average PCB concentration to 30 inches or depth of removal
  - Evaluated on basis of removal segments
  - Combined results from samples collected by ARCADIS and MDEQ when both present in a removal segment
- **No materials require TSCA disposal**
  - Five removal segments contained either sediment or soils with maximum PCB concentration > 50 mg/kg PCB
  - Depth-weighted average PCB concentrations over removal depths in these five removal segments range from 34.6 to 42.5 mg/kg



# Removal Segments with Max PCB > 50 mg/kg





# TSCA Disposal Evaluation According to Fox River Protocol

Location	MDEQ Sample ID	Removal Depth	Sample Interval		Thickness (in)	ARCADIS PCB (mg/kg)	MDEQ PCB (mg/kg)	Average PCB (mg/kg)	Depth-Weighted PCB	TSCA Determination
			Top (in)	Bottom (in)						
P2FP-053	N/A	12 inches	0	6	6	13 J			36.5	Non-TSCA
			6	12	6	60 J				
			12	24	12	0.92				
P2RT-6-2	N/A	18 inches	0	2	2	43.4			34.6	Non-TSCA
			2	6	4	100				
			6	12	6	22.6				
			12	18	6	0.086				
			18	24	6	0.086				
			24	27	3	0.054				
P2BN-23	PSD-36 and PSD-37	12 inches	0	6	6	0.88	80	41	36.9	Non-TSCA
			6	12	6	0.27	66	33		
			12	14	2	0.27	66	33		
			14	21	7	ND (0.064 U)		0.032		
P2BN-24	PSD-36 and PSD-37	12 inches	0	6	6	1.1	80	41	37.1	Non-TSCA
			6	12	6	0.46 J	66	33		
			12	20	8	0.13		0.13		
			20	24	4	ND (0.082 U)		0.041		
P2BN-26	PSL-40	24 inches	0	6	6	7.6 J	47	27		Non-TSCA
			6	8	2	8.4 J	47	28		
			8	12	4	8.4 J	73	41	42.5	
			12	19	7	45	73	59		
			19	23	4	45		45		

	Non-TSCA
	Not included in calculation



# Schedule



# Estimated Planning and Removal Action Schedule

## Plainwell No. 2 Dam Area

2009 - Q1    2009 - Q2    2009 - Q3    2009 - Q4    2010 - Q1    2010 - Q2    2010 - Q3  
 Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep

### Administrative Process

Meeting with USEPA and MDEQ to finalize scope  
 Preparation of Work Plan for AOC  
 Working Meeting to finalize Scope  
 Finalization of Work Plan for AOC  
 Obtain Access Agreements  
 Finalization of AOC Document  
 Preparation of USEPA Action Memo  
 Public Meeting to Describe Project Scope and Schedule

4/13

### Design Process

Prepare Draft Design Documents  
 Review of Draft Design by Agencies/Trustees  
 Prepare Final Design Documents  
 Review of Final Design by USEPA and working meetings if needed  
 USEPA Approval of Remedial Action Design

### Implementation

Mobilization/Staging/Access/Clearing  
 Year 1 Removal Actions  
 Year 2 Removal Actions







4-13-09  
Comp. Call 0830  
GP  
ARCADIS  
MDEQ  
EPA

Settlement Confidential – FOIA Exempt

# Proposed Scope for Focused Cleanup of Plainwell No. 2 Dam Area

April 13, 2009





# Background

- KRSG, USEPA, MDEQ, and Natural Resource Trustee met 10/07/08 to review KRSG's proposed *Next Steps for Cleanup and Restoration of the Kalamazoo River*
  - Included scope for cleanup of Plainwell No. 2 Dam Area
- *Conceptual Design Report for Bank Removal and Restoration – Plainwell No. 2 Dam Area* (CDR) submitted to USEPA 11/04/08
- A meeting was held 12/04/08 to discuss Agencies' review of the CDR
- Additional data from MDEQ forwarded to KRSG on 12/29/08
- A planned January 2009 meeting to complete scope discussions was canceled by Millennium Holdings, LLC
- ARCADIS reconnoitered Island 2 side channel area in February 2009
- This updated proposed scope for jointly funded cleanup agreement with USEPA was modified in response to Agency comments on the initial proposal, and additional information from MDEQ




# Summary of Scope Adjustments from Conceptual Design Report

- Information from MDEQ was incorporated to generate updated cumulative mass removal basis for targeting bank segments
  - New bank segments included near the Dam, Island 2 side channel
  - PCB mass removal increased to 92% of available inventory
  - Bank removal increased to 53% of total length
- 0.9-acre floodplain area near mouth of oxbow with 44 (J) mg/kg PCB in the surface soil (0 to 0.5-foot interval) included
- Remaining floodplain and bank soil PCB concentrations average 2.3 mg/kg with a median of 1.3 mg/kg
- 0.9-acre sediment area on west side of oxbow included down to midpoint between sediment samples P2RT7-7 and P2RT8-7
- Removal of toe-of-bank sediments in specific areas
  - To be determined in design based on individual transect information
  - Allowed for using 1.5 ft<sup>2</sup> cross-sectional excavation along length of removed bank




# Proposed Removal Areas






# Removal Scope: Proposed Bank Soil PCB Mass Removal





# Removal Scope: Proposed Bank Soil PCB Mass Removal





# Scope Summary

*fish tissue sample in conjunction activities - sample pre + post removal ~~into~~*

Parameter	Extent of Removal
Bank Length	2.1 miles
Bank Area	7.1 acres
Bank Soil Volume	11,200 cy
Floodplain Area	0.9 acres
Floodplain Volume	780 cy
Sediment Volume	2,290 cy
<b>TOTAL VOLUME</b>	<b>14,270 cy</b>



# TSCA Disposal Requirements

*Big Issue for GP.*

- **Application of Fox River Protocol**

- Depth-weighted average PCB concentration to 30 inches or depth of removal
- Evaluated on basis of removal segments
- Combined results from samples collected by ARCADIS and MDEQ when both present in a removal segment

*Fox River 30" protocol was for a incineration sediment removal w/ cutter head dredge vs. bank and excavation*

*GP doesn't want to change this afraid of setting precedent w/ 12" lifts on future work*


- **No materials require TSCA disposal**

- Five removal segments contained either sediment or soils with maximum PCB concentration > 50 mg/kg PCB
- Depth-weighted average PCB concentrations over removal depths in these five removal segments range from 34.6 to 42.5 mg/kg

*GP - gather disposal facilities permit and review the designation of PCB waste (i.e. definition).*



# Removal Segments with Max PCB > 50 mg/kg





# TSCA Disposal Evaluation According to Fox River Protocol

Location	MDEQ Sample ID	Removal Depth	Sample Interval		Thickness (in)	ARCADIS PCB (mg/kg)	MDEQ PCB (mg/kg)	Average PCB (mg/kg)	Depth-Weighted PCB	TSCA Determination
			Top (in)	Bottom (in)						
P2FP-053	N/A	12 inches	0	6	6	13 J			36.5	Non-TSCA
			6	12	6	60 J				
			12	24	12	0.92				
P2RT-6-2	N/A	18 inches	0	2	2	43.4			34.6	Non-TSCA
			2	6	4	100				
			6	12	6	22.6				
			12	18	6	0.086				
			18	24	6	0.086				
			24	27	3	0.054				
P2BN-23	PSD-36 and PSD-37	12 inches	0	6	6	0.88	80	41	36.9	Non-TSCA
			6	12	6	0.27	66	33		
			12	14	2	0.27	66	33		
			14	21	7	ND (0.064 U)		0.032		
P2BN-24	PSD-36 and PSD-37	12 inches	0	6	6	1.1	80	41	37.1	Non-TSCA
			6	12	6	0.46 J	66	33		
			12	20	8	0.13		0.13		
			20	24	4	ND (0.082 U)		0.041		
P2BN-26	PSL-40	24 inches	0	6	6	7.6 J	47	27		Non-TSCA
			6	8	2	8.4 J	47	28		
			8	12	4	8.4 J	73	41	42.5	
			12	19	7	45	73	59		
			19	23	4	45		45		

	Non-TSCA
	Not included in calculation